

17 Harrison Street
Marshalltown

P O Box 61542
Marshalltown 2107
Tel : (011) 688-1400 Fax : (011) 688-1556



Johannesburg Water

PAGE NO.	
1 of 1	
CLOSING DATE AND TIME	
13-May-21	12:00
Date of Issue	
04 May 2021	
VALIDITY	

INITIATING DEPARTMENT	INITIATOR
BWW - Northern Works	Bonga
QUOTATION REFERENCE	COLLECTIVE NO.
RFQ JW078KP 2021	
QUOTATION REQUESTED FROM	

REQUEST FOR QUOTATION

QUOTATION DATE

QUOTATIONS WILL BE EVALUATED ON THE 80/20 POINT SCORING SYSTEM.80 POINTS WILL BE ALLOCATED TO PRICE AND THE REMAINING 20 POINTS WILL BE ALLOCATED FOR BBBEE AND PREFERENTIAL PROCUREMENT ALL SUPPLIERS RESPONDING TO QUOTATIONS SHOULD BE REGISTERED ON CENTRAL SUPPLIER DATABASE(CSD)

JW CONTACT PERSON: kakaretso Phiri e-mail address:kakaretso.phiri@jwater.co.za.....

TELEPHONE NUMBER:011 688 1533

ITEM NO.	DESCRIPTION	BRAND NAME OFFERED	UOM	QTY REQUIRED	PRICE QUOTED EXCL. OF V.A.T.	DIS
	Unit 5 Final Effluent Pump Station cable Restoration					
1	Supply, Install, Terminate and Commission, 120sqmm 4 Core from MCC to the joint		Metres	30		
2	Supply, Install a heat shrink joint for the above cable		each	1		
3	Drain water from the cable ducting and install a drainage point for water		Sum	1		
4	Supply and replace all the smaller cables that were cut <i>(sizes will be determined during the site visit)</i>		Sum	1		
5	Supply, Install stainless steel cable tray covers		Metres	50		
6	Allow for removal and restoration of concrete slabs with replacement of all the broken ones		Sum	1		
7	Supply, Install, Terminate and Commission, 35sqmm 4 Core from MCC to Online Monitor Room DB		Metres	30		

to kakaretso.phiri@jwater.co.za; late quotes will not be considered
Quotations must indicate subtotal and also total inclusive of VAT for suppliers who are VAT registered

Note 1: All cables should be manufactured to SANS SANS 1507-3 and must be copper conductors, PVC insulated, PVC bedded, SWA, PVC sheathed, 600/1000V
Note 2: Provision should be made for the lifting and putting back of cable trench covers (steel and concrete blocks) as well as breaking/removal and replacing of sand and concrete screed on the platforms
Note 3: All measurements to be confirmed on site
Note 4: Provision should be made for all the needed assesories such as Cable Glands, ferrules, lugs, crimping tools etc.
NNB: Site visit is compulsory for verification of specifications, equipments and ensuring Health and Safety. Northern WWTW (Google Maps), 388JR, Diepsloot, 2069 Site briefing date: 06 May 2021 @ 09h30am For More Information Contact: Bonginkosi Kunene at 066

SUPPLIER DETAILS	CONDITIONS
OFFICIAL STAMP	1. QUOTATIONS RECEIVED AFTER CLOSING TIME ON THE CLOSING DATE WILL NOT BE ACCEPTED.
AUTHORISED BY:	2. QUOTATIONS WITHOUT BRAND NAMES WHERE REQUIRED WILL NOT BE ACCEPTED
SIGNATURE:.....	3. PRICES QUOTED MUST BE AS PER THE UNIT INDICATED AND BE EXCLUDED OF VAT
DATE:.....	4. QUOTATIONS WITHOUT THE SUPPLIER'S AUTHORIZED SIGNATURE WILL NOT BE ACCEPTED.
	5. ACCEPTANCE OF A QUOTATION WILL BE SUBJECT TO JOHANNESBURG WATER'S SUPPLY CHAIN POLICY